



| MATERIALS | | |
|-----------|------|----------------------------------|
| ITEM | QTY. | DESCRIPTION |
| 1 | 1 | BACKFLOW PREVENTION ASSEMBLY |
| 2 | - | 4" CONCRETE SLAB |
| 3 | 1 | AMR BADGER WATER METER |
| 4 | 2 | RISERS - GALVANIZED OR BRASS |
| 5 | 3 | ELBOWS - GALVANIZED OR BRASS |
| 6 | 5 | 4" NIPPLES - BRASS OR GALVANIZED |
| 7 | 1 | CURBSTOP WITH WING LOCK |
| 8 | 2 | BRASS SPUDS ADAPTORS |
| 9 | 2 | BRASS SPUDS - METER CONNECTIONS |
| 10 | 1 | ADJUSTABLE PIPE SUPPORT |

NOTES:

1. FIELD ADJUST AND CUT ITEM #4 TO THE PROPER LENGTH.
2. CONCRETE SLAB SHALL BE 4" THICK AND EXTEND 12" MINIMUM AROUND ENTIRE INSTALLATION.
3. BACKFLOW PREVENTION ASSEMBLY SHALL BE INSTALLED IN AN ACCESSIBLE LOCATION TO FACILITATE INSPECTION AND SERVICING: A MINIMUM OF 12" FROM ANY STRUCTURES OR OBSTACLES.
4. ONLY PIPE AND FITTINGS TO BE PAINTED SAFETY BLUE.
5. SEE CITY OF PLANT CITY APPROVED LIST OF BACKFLOW PREVENTION ASSEMBLIES.
6. BOLLARDS AS REQUIRED IN HIGH TRAFFIC AREAS, PAINTED OSHA SAFETY YELLOW.

City of Plant City
 1802 Spooner Drive
 Plant City, FL 33563
 Phone: (813) 757-9288



ABOVE GROUND METER INSTALLATION SINGLE SERVICE
 WITH BACKFLOW PREVENTION ASSEMBLY
 $\frac{3}{4}$ " TO 2"

ORIGINAL DRAWING 10/03/2017

SCALE: NTS

DRAWING NO.

WS-13

REVISION DATE

PAGE NO.

REVISION DATE

17

REVISION DATE