

NOTE: FOR COMMERCIAL RECLAIMED WATER INSTALLATION ONLY IF CHEMICALS ARE NOT ADDED TO THE CUSTOMER'S SYSTEM.

	MATERIALS	
QTY.	DESCRIPTION	
1	BADGER AMR RECLAIMED WATER METER	
2	RISERS - GALVANIZED OR BRASS	
3	ELBOWS - GALVANIZED OR BRASS	
4	4" NIPPLES - BRASS OR GALVANIZED	
1	CURBSTOP WITH WING LOCK	
2	BRASS SPUD ADAPTORS	
2	BRASS SPUDS - (METER CONNECTIONS)	
	CONCRETE SLAB 4"	
	QTY. 1 2 3 4 1 2 2 -	

NOTES:

- FIELD ADJUST AND CUT ITEM #2 TO THE PROPER LENGTH.
 CONCRETE SLAB SHALL BE 4" THICK AND EXTEND 12" MINIMUM AROUND ENTIRE INSTALLATION.
 PIPE AND FITTINGS TO BE PAINTED PANTONE PURPLE.
- 4. BACKFLOW ASSEMBLY SHALL BE INSTALLED IN AN ACCESSIBLE LOCATION TO FACILITATE INSPECTION AND SERVICING: A MINIMUM OF 12" FROM ANY STRUCTURES OR OBSTACLES.
- 5. SEE CITY OF PLANT CITY LIST OF APPROVED BACKFLOW PREVENTION ASSEMBLIES.
- 6. BOLLARDS AS REQUIRED IN HIGH TRAFFIC AREAS, PAINTED OSHA APPROVED SAFETY YELLOW.

City of Plant City 1802 Spooner Drive Plant City, FL 33563 Phone: (813) 757–9288



ABOVE GROUND RECLAIN INSTALLATION SIN 1-1/2" 7	DRAWING NO.		
ORIGINAL DRAWING 10/03/2017	SCALE: NTS	RS-3	
REVISION DATE		PAGE NO.	
REVISION DATE		49	
REVISION DATE		49	